



**This material developed through the
2012 SEET Technology Workshop**

- **Don Davis**
University of New Mexico,
Los Alamos & Los Alamos High
School
- **Rick Eckstrom**
Technical College of the
Lowcountry, South Carolina
- **Fred Hopps**
North Shore Community College,
Massachusetts
- **Mary Marchegiano**
Delaware Technical & Community
College
- **Peter Parrish**
College of the Canyons,
California



Organization of Webinar



- System Design
 - Determine customer needs.
 - Perform site survey.
 - Document size and condition of service panel, and location of utility disconnect.
 - Develop detailed engineering plans: mechanical and electrical.
- The Permit Package
 - Assemble documentation package and submit permit application to Building and Safety/Fire Departments for review and approval.
 - Utility company performs “PV service spot” & issues their interconnection requirements.
- System Installation
- Post Installation
 - Approvals
 - Building and Safety
 - Utility company
- Instruction Ideas
- Next Steps...



System Design



Design Sequence

- Start with customer usage and tariffs (salesperson).
 - 12 months of history to average out seasonal variations
 - Determine the applicable rate: flat rate, seasonal rates (summer/winter), time-of-use rates, or tiers (the more you use, the more it costs!)
- Customer strategy and budget (salesperson)
 - Eliminate bill
 - If time-of-use, shift loads to base period and add solar to eliminate peak and shoulder usage.
 - If tiers, employ peak shaving.

Design Sequence (cont)

- Back-of-envelope estimates (salesperson)
 - 4.25 kWh/d/kWh
 - South-facing roof produces 10 W/sq. ft.
 - \$6.00/W-dc
 - ~ 10 year payback, 6-8% Return on Investment (ROI)
- Prediction of system performance (with software)
- Google Earth & Bing/Zillow (salesperson)
 - Identify premium roof space
 - Preliminary layout
- Site survey (surveyor)
- Detailed design (engineer)





System Design



Case Study

- Customer wants to eliminate their electricity bill.
 - Energy usage: 6,600 kWh/yr (550 kWh/mo; 18.1 kWh/d)
 - Small home (2,000 sq. ft.)
- Design constraints
 - BP Solar BP175B modules
 - Inverter SMA SB4000US
- System simulation tools
 - PV WATTS2 or other software
 - Inverter string sizing: basically checking voltages
 - www.weather.com for record low & average high temperatures (needed for string sizing)



Site Survey Results


- Customer roof section
 - Roof pitch is 5:12
 - Azimuth 225 degrees (SW)
 - Some shading
 - Some minor roof damage (documented)
- Candidate system 4.3 kWdc
 - 24 ea BP-175B
 - 1 ea SMA SB4000US

Physical Layout—Preliminary

- Google Earth
 - 13 ft. ridge to eaves
 - 22 ft. along ridge
 - 36 ft. along eaves
 - Orientation 235° true
- Bing/Zillow
 - Roof pitch 3:12 (14°)
- Preliminary layout
 - Look at obstructions.
 - Observe shading.
 - Calculate setbacks for fire dept.



Preliminary Layout





System Design



PVWatts2 Simulator

Site Location:

Cell ID: 0175361
 State *: California
 Latitude *: 34.075
 Longitude *: -117.951

PV System Specifications:

DC Rating (kW):
 DC to AC Derate Factor:
 Array Type:
 Fixed Tilt or 1-Axis Tracking System:
 Array Tilt (degrees): (Default = Latitude)
 Array Azimuth (degrees): (Default = True South) [What's this?](#)

Energy Data:

Cost of Electricity (cents/kWh):

Roof space limitations
 reduce system to 18
 modules or 3.15 kWdc

PVWatts2 Simulator (cont)

Calculator for Overall DC to AC Derate Factor

Component Derate Factors	Component Derate Values	Range of Acceptable Values
PV module nameplate DC rating	<input type="text" value="0.95"/>	0.80 - 1.05
Inverter and Transformer	<input type="text" value="0.96"/>	0.88 - 0.98
Mismatch	<input type="text" value="0.98"/>	0.97 - 0.995
Diodes and connections	<input type="text" value="0.995"/>	0.99 - 0.997
DC wiring	<input type="text" value="0.98"/>	0.97 - 0.99
AC wiring	<input type="text" value="0.99"/>	0.98 - 0.993
Soiling	<input type="text" value="0.97"/>	0.30 - 0.995
System availability	<input type="text" value="0.98"/>	0.00 - 0.995
Shading	<input type="text" value="0.98"/>	0.00 - 1.00
Sun-tracking	<input type="text" value="1"/>	0.95 - 1.00
Age	<input type="text" value="1"/>	0.70 - 1.00
Overall DC to AC derate factor	0.803	

PVWATTS2 Simulator

Station Identification		Results			
Cell ID:	0175361	Month	Solar Radiation (kWh/m ² /day)	AC Energy (kWh)	Energy Value (\$)
State:	California	1	3.40	248	33.48
Latitude:	34.1 °N	2	4.17	278	37.53
Longitude:	118.0 °W	3	5.17	382	51.57
PV System Specifications					
DC Rating:				430	58.05
DC to AC Derate Factor:				505	68.17
AC Rating:				526	71.01
Array Type:	Fixed Tilt	7	7.43	518	69.93
Array Tilt:	14.0 °	8	6.97	487	65.75
Array Azimuth:	235.0 °	9	5.94	403	54.41
Energy Specifications		10	4.70	336	45.36
Cost of Electricity:	13.5 ¢/kWh	11	3.82	266	35.91
		12	3.13	226	30.51
		Year	5.46	4604	621.54

12.6 kWh/d / 3.15 kWdc = 4.0
Shading 98%, Soiling 97%, SW

- 8.0**
- 9.9**
- 12.3**
- 14.3**
- 16.8**
- 17.5**
- 16.7**
- 15.7**
- 13.4**
- 10.8**
- 8.9**
- 7.3**
- 12.6**



System Design



SEC# 2016 CITY OF GLENDALE WATER & POWER PHOTOVOLTAIC SERVICE SPOT PV METER

JOB ADDRESS 6671 W 116th St PK SERVICE SPOT DATE 2-2-10
 PROJECT NUMBER 11674 SERVICE SPOT BY GILBERT
 OFFICE (818) 548-3200 FAX (818) 240-4754

-IF A REVISION OF THIS SPOT IS REQUESTED, A MIN. \$65.00 FEE WILL APPLY
 -SPOT IS VALID FOR TWO YEARS FROM DATE OF SPOT

REQUIREMENTS:

- SIGNED PHOTOVOLTAIC INTERCONNECTION AGREEMENT ON FILE WITH CUSTOMER SERVICE ELECTRIC ENGINEERING SECTION BEFORE BUILDING AND/OR ELECTRIC PERMITS ARE SIGNED AND SERVICE SPOT IS RELEASED TO CONTRACTOR OR HOMEOWNER.
- METER SOCKET CLEARANCE TO SIDEWALLS / OBSTRUCTIONS: 10" MIN.
- SERVICE CONNECTION WILL NOT BE MADE UNTIL:
 - APPLICATION FOR BUILDING AND/OR ELECTRICAL PERMIT(S) ARE SIGNED AT 141 NO. GLENDALE AVENUE, 4TH LEVEL, GLENDALE, CA 91206-4496. WATER & ELECTRICAL SERVICES COUNTER (818) 548-3921.
 - OBTAIN ELECTRICAL PERMIT AT 633 E. BROADWAY, PERMIT SERVICES CENTER, ROOM 101, (818) 548-3200.
 - LABEL SERVICE METER, SERVICE METER DISCONNECT, PV METER, & PV METER DISCONNECT PER BUILDING & SAFETY REQUIREMENTS.
 - REQUEST A FINAL BUILDING & SAFETY INSPECTION BY CALLING (818) 548-4830.
 - REQUEST A FINAL GWP CONSTRUCTION INSPECTION BY CALLING (818) 548-3920.
 - AFTER GWP RECEIVES THE INSPECTION RELEASES FROM BUILDING & SAFETY INSPECTOR AND GWP CONSTRUCTION INSPECTOR, ALLOW 7 TO 10 WORKING DAYS FOR GWP TO INSTALL THE PHOTOVOLTAIC METER AND SEAL THE METER.

CONTACT GWP CONSTRUCTION INSPECTOR (818) 548-3920, 48 HOURS IN ADVANCE FOR A PRECONSTRUCTION MEETING REGARDING: AC DISCONNECT AND GWP PV METER.

THE DISCONNECT OPERATING HANDLE IS TO BE NO HIGHER THAN 6'-7" FROM GRADE WHEN THE HANDLE IS IN THE HIGHS. SECTION _____
 THE PV SYSTEM SHOULD NOT BE ENERGIZED / ACTIV. D UNTIL _____
 PROCESSES OUTLINED ABOVE IN STEPS 1 THROUGH 3. COMPL. _____
 PV METER SOCKET TO BE RING TYPE.
 MAXIMUM PV BREAKER SIZE 20A

***AC DISCONNECT TO BE PAD-LOCKABLE IN OPEN POSITION**

EXISTING METER PANEL
 PV METER & AC DISCONNECT
 POLE #28949-A
 28949-A (1) 5/5 150' W/O A.A.V.

3' CLEAR LEVEL WORK SPACE IN FRONT OF ELECTRICAL EQUIPMENT

28949-A (1) 5/5 150' W/O A.A.V.

CUSTOMER METER SHOP BUILDING AND SAFETY CONST. INSPECTOR LOG IN APPD WJ 2-5-10 SHEET _____ OF _____



System Design



Detailed Financials—Flat Rate


- Price: $\$6/\text{Wdc} * 3,150 \text{ Wdc} = \$18,900$
- Rebate (state or local): $\$4,725$
- Contract for $\$14,175$
- Federal tax credit: $\$4,253$
- 1st year energy bill savings: $\$622$
- Out-of-pocket at Year 1 = $\$9,300$
- Break even at 11 years
- IRR = 6%




Physical Layout

- Starting from preliminary layout
 - Precise layout specifying exact location of anchors, rails and modules
 - Anchors must be located on rafters (16” spacing in most cases)
 - End module cannot cantilever more than 50% beyond last anchor
 - Minimize shading and avoid obstructions
- Bill of materials (racking hardware)
 - Anchors
 - Flashing
 - Rail (piece lengths) and possibly splices
 - Module brackets (center and end)

PV System Components



Single Line Diagram





The Permit Package



Electrical Calculations

- DC string sizing
 - $V_{max} = N * V_{oc} (T_{rec-low}) < 600 \text{ V-dc}$
 - $I_{max} = I_{sc} * 1.25 * 1.25$
 - Select wire gauge and temperature rating.
 - Ampacity of wire corrected for temperature and conduit fill
 - Temperature of conduit exposed to sunlight on rooftops can be 14°C to 33°C above ambient.
- AC wiring
 - $I_{max} = P_{max} / 240 \text{ V}$
 - $I_{output} = I_{max} * 1.25$
 - Select wire gauge and temperature rating.
 - Ampacity of wire corrected for temperature and conduit fill
 - OCP device $< I_{output}$ (Always round up.)



The Permit Package



Document ID: 145376
DR

Permit Number: BC 2010
Plan Check Number:

Printed On: 13-MAY-10

Expiration Date: 09-NOV-10

CITY OF GLENDALE - BUILDING AND SAFETY
633 E. Broadway, Rm. 101
Glendale, CA 91206 • (818) 548-3200 (818) 548-4830 (TDD)

Permit Status: OPEN
Status Date: 13-MAY-2010

81020
SFD-ALTERATION/REPAIR
Combination Bldg./Trade Permit

Scope of Work
PV SYSTEM INSTALLATION W/ELECTRIC

Individual's / Company Name	Address / City, State Zip	City, State Lic. / Worker's Comp.	Phone Number
(APP) California Soar Engineering (OW) California Soar Engineering (CNT) California Soar Engineering	820 CYNTHIA AVE Los Angeles, Ca 90065 820 Cynthia Ave Los Angeles, Ca 90065	GRABER ET AL COACHING/CDRP/PTI	323-256-8883

Tract Name / Number	Block(s)	Lot(s)	Assessor's ID
	GC	GC	5-00

Estimated Value: Calculated Value: \$15,000

Permit Quantities	City Comments or Y/N	Permit Quantities	City Comments or Y/N

Comments	Amount	Fee Description	Amount
COMBINATION BUILDING/ALL	\$265.18	GREEN BUILDING	\$0.90
GREEN BUILDING ADMINISTRATION	\$0.10	MICROFILM	\$43.26
PLANNING SURCHARGE	\$17.77	TECHNOLOGY SURCHARGE	\$18.03
Total Fees Due:	\$0.00	Total Fees Paid:	\$345.24

Clearance Agency	Activity Code	Status	By	Date	Signature	Date
BUILDING	DONE	YCRISIS	13-MAY-10			
BUILDING	OPEN					
FIRE	DONE	PMC/LEAN	13-MAY-10			
Condition Code	Status	By	Date			
WATER	DONE	GARTERAGA	13-MAY-2010			

The person signing for this permit acknowledges that there are NO Oak, Bay or Sycamore Trees with trunks larger than an eight inch (8") diameter within a twenty foot (20 ft) influence of the proposed construction.

At the time of final inspection, the inspector shall verify the installation of smoke detectors in all sleeping rooms and hallways leading therein. Battery operated smoke detectors are acceptable in existing construction.

*** No rooftop equipment will be allowed unless the applicant obtains a separate variance or administrative exemption from the Planning Division. Issuance of this permit shall not be construed as an approval to install equipment on the roof without a variance or administrative exemption.

*** Issuance of trade permits, without complete architectural plans, shall not constitute a waiver of any provisions of the building or zoning codes of the City of Glendale. It is the responsibility of the applicant to verify that approved installations are in compliance with the regulations of all applicable codes or else obtain written approval for any deviations from the regulations.

*** Upon completion of the work authorized by this permit, the permittee shall notify the Building Inspection office of such completion by requesting the Final Inspection. Such request can be made by calling (818) 548-3130. The permittee is hereby advised that there may be entitled to reimbursement of the permit fees if the city fails to conduct an inspection of the completed work within 10 days of the request for final inspection.

*** No construction is permitted before 7 a.m., and after 7 p.m., Monday through Saturday. No construction is permitted on Sundays or on holidays. (Man. Code Sec. 8.26.080)

The City of Glendale reserves issuance of the building permit to the property owner or licensed general contractor only. Signatures of this individual must be verified by personal identification. Any person signing the permit application as agent for the owner or contractor shall have an original letter of authorization on the face of permit application.

Applicant shall retain 100 days after the date of substantial completion as required by sec. 187.4 of the Glendale Building Code, and thereafter, any documents submitted to the department shall be returned to the applicant or destroyed by the building official. Upon written request from the applicant, the building official may extend the period of permit application.



System Installation



- Anchor and rail installation
- Module mounting
- Junction box installation
- Inverter installation
- Final completion of the array circuit

System Installation

Know how to use and put on your safety gear.



System Installation

Correctly install safety anchor points.



System Installation

Lay out chalk lines and measure for mounting bracket holes.



System Installation

Position modules in landscape mode with vertical rails.



System Installation

Install rails to anchors.



<http://www.youtube.com/v/ir9c0zCbEF0>

System Installation

Check for squareness by equating the diagonals.



System Installation

Position module junction box to facilitate wiring, attach ground wire, position module, and install end clamps.



<http://www.youtube.com/v/0-FxFjtLE1E>

System Installation



<http://www.youtube.com/v/1poG-A-zQSI>

System Installation

Install ground wire and second module.



http://www.youtube.com/v/rl-8_MF31A8

System Installation

Connect wires in the string.



http://www.youtube.com/v/E_C_-SBP4QU

System Installation

Install remaining modules.



System Installation

Connect PV wires to the Soladeck combiner/junction box that feeds through roof to attic space.



System Installation

The Soladeck enclosure




System Installation

Attach conduit from Soladeck on roof to junction box in attic.



System Installation




System Installation

Net meter



DC disconnect with lockout/tagout



System Installation

Checking for array voltages and polarities



System Installation

Inverter is powered up and begins a 5-minute “countdown” before producing AC power.





Post Installation



- Commissioning & certification
- Inspections
 - Building and safety
 - Utility
- Owner's manual

- Document system:
 - Date, time, ambient temp, irradiance
 - Lead installer
 - Person doing certification
- Specify manufacturer and model no.:
 - PV Module
 - Inverter
 - DC & AC disconnects
- Document:
 - DC measurements
 - Number of modules/string and number of strings
 - Open circuit string voltages ($V+$ to $V-$, $V+$ to gnd, $V-$ to gnd)
 - String voltages under load
 - AC measurements
 - L1 – L2, L1 – neutral, L2 – neutral voltages
 - AC power and cumulative energy produced





Example of Certification Sheet



California Solar Engineering, Inc. PV System Certification Sheet

System Information										
Customer Name:					Date Certified:					
Address:					Certified By:			Lead Installer:		
City/State/Zip:					DC Disconnect(s)			AC Disconnect		
System Size in kW:					Size				Size	
Modules	Total #:	Make/Model:			Make				Make	
Main Panel PV Breaker size:					Model#				Model#	
Time:			Weather:			Temperature (estimate) °F:				
Inverter #	1	2	3	4	5					
Inv. Make										
Inv. Model										
Inv. Ser #										
A/C Watts (Now)										
A/C Test Data										
Inverter #	1	2	3	4	5					
VAC @ Inv (measured L1-L2)										
L1 V - Ground (measured)										
L2 V - Ground (measured)										
D/C Test Data (Voltmeter)										
String Number	1	2	3	4	5	6	7	8	9	10
Source Ct ID (if used)										
Inverter #										
Total# Modules										
Open Ct V (+/-)										
Volts (+) to Ground (actual reading)										
Volts (-) to Ground (actual reading)										



Applicable Codes



- NEC 2011
- NFPA 70
- IRC or IBC
- California State Fire Marshal: Solar Photovoltaic Installation Guideline; “Final Draft”; April 22, 2008
- Contact your state, and county/city authorities for additional rules and procedures.

Instruction Ideas

Photo Credit: In Shik Lee



Instruction Ideas

SEET 2012 Workshop Basic Solar Photovoltaic System Design

EXERCISE A:
Using the resources provided below, show appropriate connections to design a 12V system with battery back up. Provide totals as specified.




Photo Credit: In Shik Lee



Next Steps...



References



- Dunlop, J.P., Photovoltaic Systems, 2nd ed., ATP Press
- Holt, M., Understanding NEC Requirements for Solar Photovoltaic Systems, 1st ed., Mike Holt Enterprises Inc.
- Solar Energy International, Solar Electric Handbook: Photovoltaic Fundamentals and Applications, 2nd ed., New Society Publishers
- www.SolarDepot.com
- www.WholesaleSolar.com



SEET



For more information on the SEET Energy Webinar Series, please contact Melonee at
ATEEC
mdocherty@eicc.edu

<http://ateec.org/ateec-downloads/ateec-downloads/>